

# CATTARAUGUS COUNTY

## DEPARTMENT OF PUBLIC WORKS

### ADDENDUM NO. 1

FOR

## YORKSHIRE BRIDGE No. 14 – DECK REPLACEMENT

MILL STREET OVER ELTON CREEK

**ADDENDUM DATE: 14 JUNE 2022**

---

**The following are clarifications to the bid specifications and plans:**

1. The cost for the sidewalk on the bridge shall be included in the bid costs for the bridge deck, Item 557.0509. No separate payment for the bridge sidewalk will be made. Provisions for sidewalks in Section 557 shall apply. Class E concrete or an allowable substitution for Class E shall be allowed. Class HP concrete will not be allowed for the bridge sidewalk.
2. All reinforcing bars used for the project shall be uncoated bar reinforcement, grade 60, meeting the requirements Section 709-01 of the Standard Specifications.
3. The County shall provide, install and maintain any additional signage required for the temporary pedestrian bridge.

**Changes to the plans and bid proposal booklet:**

Plans: Sheet 2 of 15: In the Table of Quantities change the estimated quantity of Item 557.950000CA – Corrosion Inhibitor for Superstructure Slabs and Structural Approach Slabs, from: “250” to “450”.

General Provisions & Bid Proposal Booklet: Page 13 (A-6, IP-5 of IP-13): Change the quantity of Item 557.950000CA – Corrosion Inhibitor for Superstructure Slabs and Structural Approach Slabs, from: “250 GAL” to “450 GAL”.

---

**ALL BIDDERS MUST RETURN THIS ADDENDUM WITH THE BID AND RECORD THIS ADDENDUM IN SECTION B ON SHEET B-2 IN THE BID PROPOSAL BOOK.**

---

**IN ADDITION, PLEASE ACKNOWLEDGE RECEIPT OF ADDENDUM 1 IMMEDIATELY BY PROVIDING THE INFORMATION BELOW AND FAXING THIS SHEET TO:**

Cattaraugus County  
Department of Public Works  
(716) 938-2754

Company Name: \_\_\_\_\_ Signed: \_\_\_\_\_

Date: \_\_\_\_\_ Printed Name of Signatory: \_\_\_\_\_